


Note B:
Station for light post support bracket shown on Plans is only approximate. φ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at φ of pier, eliminate the control joint at the φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

PLAN
Scale: 1/2"=1'-0"



SECTION A-A
Scale: 1/2"=1'-0"

Note:
Normal deck reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

34" STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 2/18/76	
REVISIONS	
SHA	FHWA
1-8-93	
9-24-96	
6-1-05	
1-9-08	

FHWA APPROVAL
DATE: 8-24-76


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH STRAIGHT BACK


STANDARD NO. BR-SS(6.04)-05-7A

SHEET 1 OF 2

SUPER-CONCRETE WORK



Note B:
 Station for light post support bracket shown on Plans is only approximate. φ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at φ of pier, eliminate the control joint at the φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
 Scale: 1/2" = 1'-0"

Note:
 Deck overhang reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

34" STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 2/18/76	
REVISIONS	
SHA	FHWA
9-24-96	
6-1-05	
10-9-07	
1-9-08	

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
 WITH STRAIGHT BACK


STANDARD NO. BR-SS(6.04)-05-7A(L)

VERIFIED
 10-9-2007
 LRFD

SHEET 1 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27A.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

34'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 2/18/76	
REVISIONS	
SHA	FHWA
8-4-92	.
9-24-96	.
8-7-98	.
6-1-05	.

FHWA APPROVAL
DATE: 8-24-76

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34'' F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.04)-05-7A

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27A.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

34'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 2/18/76	
REVISIONS	
SHA	FHWA
9-24-96	.
8-7-98	.
6-1-05	.
10-9-07	.

FHWA APPROVAL
DATE: 8-24-76

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH STRAIGHT BACK


STANDARD NO. BR-SS(6.04)-05-7A(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK



Note B:
 Station for light post support bracket shown on Plans is only approximate. Φ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at Φ of pier, eliminate the control joint at the Φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A

Scale: $\frac{1}{2}''=1'-0''$

For Section "B-B" see Sheet 2 of 2.

Note:
 Normal deck reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

42'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.

FHWA APPROVAL
 DATE: .

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH SINGLE CONDUIT AND 42'' F-SHAPE PARAPET
 WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.04)-05-7B

SHEET 1 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to deck overhang steel. Hook one end.

Provide slip hole or drill and tap box for 1 1/4" ϕ conduit.

ϕ 4" ϕ conduit, full length of bridge.


#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.


4-#5 \sqsubset Ties

Spacing to match that of deck overhang steel (Varies 5" to 7"). Bars to be placed between deck overhang steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.



Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

42" STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.04)-05-7B(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27B.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

42'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE:	


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.04)-05-7B

SHEET 2 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27B.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

42'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	.
.	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.04)-05-7B(L)


SHEET 2 OF 2

SUPER-CONCRETE WORK



Notes:

1. * Omit concrete haunch by dropping bottom of concrete slab to bottom of top flange on spans of 30'-0" or less c/c of bearings.
2. Dimension 'S' at either edge of stringer, for its full length, as shown above, must not be less than dimension 'T', therefore, check this dimension along both edges of stringers at each elevation point shown on "Bridge Deck Elevation" sheet prior to placing any form work. In determining the depth of haunch for continuous bridges the span length shall be considered to be the distance from the abutment support to the dead load contraflexure for end spans and between the contraflexure points for intermediate spans. Where cover plates and/or varying thicknesses of top flanges are utilized, this increase in depth shall be taken into account in determining the slab plus haunch thickness at ϕ of bearing.



FHWA APPROVAL
DATE: 8-24-76

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 2/18/76	
REVISIONS	
SHA	FHWA
5-14-76	10-3-80
.	.
.	.

STANDARD NO. BR-SS(6.05)-75-19


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

CONCRETE HAUNCH DETAIL
DECKS FORMED WITH TIMBER

SHEET 1 OF 1

FOR OFFICE USE ONLY

SUPER - CONCRETE WORK



SECTION
Scale: 1" = 1'-0"

* In order to insure a smooth and acceptable surface, 420.03.11 (Construction joints) will be strictly adhered to.

** Slab depth minus 1".

Notes:

1. All longitudinal bars are #5 spaced as shown and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge.
2. Key is nominal size.
3. Front face of parapet to be dimensioned from a plumb line.
4. All reinforcing steel to be epoxy coated.
5. Concrete deck reinforcing steel not shown.

34' STRAIGHT BACK TL-4 BRIDGE RAILING


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 2/25/77	
REVISIONS	
SHA	FHWA
1-4-94	.
6-27-94	.
10-22-03	.
11-26-07	.

FHWA APPROVAL
DATE: 7-15-03

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
LEVEL OR LOW SIDE OF CROWN (OR
SUPERELEVATED) SECTION OF 34" F-SHAPE
PARAPET WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.02)-03-27A

SHEET 1 OF 2



Front face configuration of parapet shall be constructed perpendicular to roadway surface.

Contractor has the option of either constructing rear face plumb or on a slope perpendicular to roadway surface. However, whatever option is chosen must be used throughout all structure(s) at a particular crossing. No additional compensation will be provided to the contractor for whatever option is chosen.

SECTION
Scale: 1" = 1'-0"

34" STRAIGHT BACK TL-4 BRIDGE RAILING

Note:
For all details not shown see sheet 1 of 2.


APPROVAL	
<i>E. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 5/14/81	
REVISIONS	
SHA	FHWA
3-9-89	3-5-90
11-7-90	.
10-22-03	.
11-26-07	.

FHWA APPROVAL
DATE: 7-15-03

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
HIGH SIDE OF CROWN (OR SUPERELEVATED)
SECTION OF 34" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.02)-03-27A

SHEET 2 OF 2



SECTION

Scale: 1" = 1'-0"

* In order to insure a smooth and acceptable surface, 420.03.11 (Construction joints) will be strictly adhered to.

** Slab depth minus 1".

Notes:

1. All #7 and #8 longitudinal bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge.
2. Key is nominal size.
3. Front face of parapet to be dimensioned from a plumb line.
4. All reinforcing steel to be epoxy coated.
5. Concrete deck reinforcing steel not shown.

42" STRAIGHT BACK TL-5 BRIDGE RAILING


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 10/22/03	
REVISIONS	
SHA	FHWA
11-26-07	.
.	.
FHWA APPROVAL	.
DATE: 7-15-03	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
LEVEL OR LOW SIDE OF CROWN (OR
SUPERELEVATED) SECTION OF 42" F-SHAPE
PARAPET WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.02)-03-27B

SHEET 1 OF 2

SUPER CONCRETE WORK



SECTION
Scale: 1" = 1'-0"

42" STRAIGHT BACK TL-5 BRIDGE RAILING


Note:
For all details not shown see
sheet 1 of 2.

APPROVAL	
<i>E. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 10/22/03	
REVISIONS	
SHA	FHWA
11-26-07	.
.	.
FHWA APPROVAL	.
DATE: 7-15-03	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
HIGH SIDE OF CROWN (OR SUPERELEVATED)
SECTION OF 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.02)-03-27B

SHEET 2 OF 2



* Slab depth minus 1".

Notes:

1. Place $\frac{1}{2}$ " saw cut joints to match joint spacing of outside parapet.
2. Concrete deck reinforcing steel not shown.
3. All #7 and #8 longitudinal bars shall be placed continuously in the barrier from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge.
4. All keys are nominal size.
5. No increase in any prices bid will be allowed for barrier modifications due to roadway slope.

42" MEDIAN TL-5 BRIDGE RAILING

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/25/77	
REVISIONS	
SHA	FHWA
9-26-89	3-5-90
10-31-90	.
10-22-03	.
11-26-07	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

42" F-SHAPE MEDIAN BARRIER FOR BRIDGE
WITHOUT LONGITUDINAL JOINT

FHWA APPROVAL
DATE:


STANDARD NO. BR-SS(6.03)-03-28

SHEET 1 OF 1


SUPER CONCRETE WORK

Notes:


1. The Contractor has the option of substituting the Ancel Frame Scaffolding System for steel forms which remain in place with the following exceptions:
 - a) Bridges over existing highways.
 - b) Bridges over high speed or electrified railroads.
2. Ancel Frames may never be used on any fracture critical member.
3. The Contractor has the option of substituting the Ancel Frame Scaffolding System for conventional overhang brackets on fascia stringers with the following exceptions:
 - a) Bridges over new or existing highways.
 - b) Bridges over navigable waterways with underclearance less than 30 feet.
4. In any instance where studs are allowed they shall remain in place.



SECTION
Scale: None



WHERE FORM IS BELOW
BOTTOM OF FLANGE
AND THERE ARE NO
SHEAR CONNECTORS



Note:
Alternate attachments will be considered, that provide the 1/2" concrete encasement of top flange.

WHERE FORM IS ABOVE
BOTTOM OF FLANGE
AND THERE ARE NO
SHEAR CONNECTORS

Notes:

1. Permanent steel deck forms and supports shall conform to 909.11. Design Span shall be the clear distance between beam and/or girder flanges less two (2) inches.
2. No welding of these forms to parts carrying tension will be permitted. These forms shall be vertically adjusted to attain line and grade as required.
3. Any permanently exposed form metal where the galvanized coating has been damaged shall be thoroughly cleaned, wire brushed and painted with two coats of zinc-oxide dust primer, Federal Specification TT-P-641d, Type II, no color added, to the satisfaction of the engineer. Minor heat discoloration in areas of welds need not be touched up.
4. Contractor has option of using this detail or that shown on 2 of 2, except for bridge decks with curved stringers or bridge with a flared rebar pattern. For bridge with curved stringers or bridge with a flared rebar pattern only the detail shown on sheet 2 of 2 can be used.
5. Where shear connectors are utilized, normal manufacturers detailing may be utilized at stringer flange.
6. Supports for rebar shall be provided by Contractor.


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 9/8/76	
REVISIONS	
SHA	FHWA
5-21-85	11-29-85
8-30-90	.
1-4-94	.
1-22-01	.

FHWA APPROVAL
DATE: 11-9-76

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
STEEL FORMS WHICH REMAIN IN PLACE
FOR CONCRETE SLABS ON STEEL STRINGERS
RE-BARS ALIGNED WITH TROUGH

STANDARD NO. BR-SS(6.06)-75-29

SHEET 1 OF 2



SECTION
Scale: None

Notes:

1. For notes see sheet 1 of 2.
2. This detail is acceptable only on structures where the General Notes under "Loading" states "and 15 pounds per square foot for use of steel bridge deck forms which remain in place."
3. Supports for rebar shall be provided by Contractor.


APPROVAL	
<i>L. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 1/29/80	
REVISIONS	
SHA	FHWA
8-30-90	.
11-18-04	.
FHWA APPROVAL	.
DATE: 6-20-80	.

**STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT**

STEEL FORMS WHICH REMAIN IN PLACE
FOR CONCRETE SLABS ON STEEL STRINGERS
RE-BARS INDEPENDENT WITH TROUGH

STANDARD NO. BR-SS(6.06)-75-29

SHEET 2 OF 2



SECTION
Scale: 1 1/2" = 1'-0"

Notes:

1. Reinforcing steel to be continuous thru joint.
2. Entire face of construction joint shall be coated with an approved epoxy bonding compound.
3. All dimensions shown are actual dimensions.
4. See lap charts for length of splices.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 1/6/78	
REVISIONS	
SHA	FHWA
12-12-83	2-23-84
7-5-84	11-8-84
12-2-87	6-8-90
3-20-95	.

FHWA APPROVAL
DATE: 1-31-78


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

BRIDGE DECK SLAB DETAIL AT
TRANSVERSE CONSTRUCTION JOINT

STANDARD NO. BR-SS(6.07)-77-68

SHEET 1 OF 1

SUPER CONCRETE WORK



PLAN

Scale: None

* Transverse construction joints to be placed parallel to center line bearing for piers and abutments. If substructure units are not parallel then transverse construction joints shall be parallel to the closest substructure unit center line of bearing.

Transverse construction joints to be perpendicular to the outside face of superstructure for the portion of the deck outside of the exterior stringer.

Note:
For detail of construction joint see
Standard No. BR-SS(6.07)-77-68.

APPROVAL	
<i>L.S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVEL.	
DATE: 4/12/78	
REVISIONS	
SHA	FHWA
12-15-80	12-15-80
9-13-94	.
FHWA APPROVAL	.
DATE: 10-17-78	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

LAYOUT OF TRANSVERSE
JOINT FOR SKEWED BRIDGE DECK


STANDARD NO. BR-SS(6.08)-78-69

SHEET 1 OF 1

SUPER-CONCRETE WORK

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

Note: Details shown are for single rail; double rail and fencing details are similar. On bridges with no fencing or railing see General Plan and Elevation for parapet control joint spacing.



ELEVATION
Scale: $\frac{3}{8}" = 1'-0"$

Note: For Section A-A & B-B see sheets 2, 3 & 4 of 4. For View D-D see sheets 2 & 3 of 4.

Notes:

- The conduit and junction box are to be placed only when indicated in the Superstructure "Typical Section." If ϕ to ϕ of end junction boxes exceed 200', then additional junction boxes shall be placed in parapet, between control joints, so that the maximum distance between boxes is 200'. Junction boxes for light standards, may be utilized. All junction boxes to have $\frac{1}{2}" \phi$ drain at drain at low point of box.
- Conduit may be either PVC or galvanized pipe.




APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 4/13/78	
REVISIONS	
SHA	FHWA
9-26-96	.
6-1-05	.
1-9-08	.
4-16-08	.

FHWA APPROVAL
DATE: 10-17-78

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK


STANDARD NO. BR-SS(6.09)-05-70A

SHEET 1 OF 4




SECTION B-B

Scale: $\frac{3}{8}'' = 1'-0''$




SECTION A-A

Scale: None



VIEW D-D - F-SHAPE PARAPET

Scale: $\frac{3}{8}'' = 1'-0''$



SECTION C-C

Scale: None

Notes:

1. Place saw cut joint at center of every rail panel.
2. Parapet is placed continuously.
3. Saw cut control joint to be sawed same day as concrete is poured.
4. Fencing and railing not shown.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 2/9/81	
REVISIONS	
SHA	FHWA
10-30-92	.
12-1-93	.
1-22-01	.
6-1-05	.

FHWA APPROVAL
DATE: 3-7-81


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK

STANDARD NO. BR-SS(6.09)-05-70A


SHEET 2 OF 4

SUPER-CONCRETE WORK



SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$


$\frac{1}{2}''\phi$ drain. Connect drain to low point of junction box. For intermediate junction boxes outlet drain thru bottom of superstructure.



VIEW D-D - PARAPET WITH SIDEWALK


Scale: $\frac{3}{8}'' = 1'-0''$

Saw cut joint do not chamfer.



SECTION A-A
Scale: None

Inside face of parapet



SECTION C-C
Scale: None

Notes:

1. Place saw cut joint at center of every rail panel.
2. Parapet is placed continuously.
3. Saw cut joint to be sawed same day as concrete is poured.
4. Fencing and railing not shown.

APPROVAL	
<i>E. Schuman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 7/12/89	
REVISIONS	
SHA	FHWA
10-30-92	
12-1-93	
6-1-05	

FHWA APPROVAL
DATE:


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK


STANDARD NO. BR-SS(6.09)-05-70A

SHEET 3 OF 4


SUPER-CONCRETE WORK



SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



SECTION C-C
Scale: Full

Notes:

1. Place vertical paraffin joint, shown hatched, at centerline of pier on multi span bridges.
2. Joints shall be formed by placing alternate sections.
3. The placement of adjacent sections shall have a 40 hour delay between placements.
4. Railing and fencing not shown.

*In order to insure a smooth and acceptable surface, 420.03.11 (Construction Joints) will be strictly adhered to.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 12/1/93	
REVISIONS	
SHA	FHWA
12-1-93	
6-1-05	
FHWA APPROVAL	
DATE:	


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK

STANDARD NO. BR-SS(6.09)-05-70A

SHEET 4 OF 4

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

Note: Details shown are for single rail; double rail and fencing details are similar. On bridges with no fencing or railing see General Plan and Elevation for parapet control joint spacing.



ELEVATION

Scale: $\frac{3}{8}" = 1'-0"$

Note: For Section A-A and B-B see sheets 2 & 3 of 3. For View D-D see sheet 2 of 3.

Notes:

- The conduit and junction box are to be placed only when indicated in the Superstructure "Typical Section." If ϕ to ϕ of end junction boxes exceed 200', then additional junction boxes shall be placed in parapet, between control joints, so that the maximum distance between boxes is 200'. Junction boxes for light standards, may be utilized. All junction boxes to have $\frac{1}{2}" \phi$ drain at drain at low point of box.
- Conduit may be either PVC or galvanized pipe.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
4-18-08	.
FHWA APPROVAL	.
DATE:	.




STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 42" F-SHAPE PARAPET


STANDARD NO. BR-SS(6.09)-05-70B

SHEET 1 OF 3


SUPER-CONCRETE WORK




SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



VIEW D-D
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION C-C
Scale: None

Notes:

1. Place saw cut joint at center of every rail panel.
2. Parapet is placed continuously.
3. Saw cut control joint to be sawed same day as concrete is poured.
4. Fencing and railing not shown.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA




FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 42" F-SHAPE PARAPET

STANDARD NO. BR-SS(6.09)-05-70B


SHEET 2 OF 3



SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



SECTION C-C
Scale: Full

*In order to insure a smooth and acceptable surface, 420.03.11 (Construction Joints) will be strictly adhered to.

Notes:

1. Place vertical paraffin joint, shown hatched, at centerline of pier on multi span bridges.
2. Joints shall be formed by placing alternate sections.
3. The placement of adjacent sections shall have a 40 hour delay between placements.
4. Railing and fencing not shown.

FHWA APPROVAL
DATE:


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND SINGLE CONDUIT
PLACEMENT WITH 42" F-SHAPE PARAPET

STANDARD NO. BR-SS(6.09)-05-70B

SHEET 3 OF 3




Notes for Additional Reinforcing:

1. These bars are required in all areas where spirals or studs exist and top of spiral or stud does not extend into hatched area.
2. These bars shall be epoxy coated.
3. The cost of these bars will be negotiated if it is found that they are necessary, unless otherwise indicated in the Special Provisions.

SECTION

Scale: 1 1/2" = 1'-0"

New shear stud developer welded to flange (Typ.). See Std. No. BR-SS(8.05)-75-30.



SPIRAL REMOVAL

Scale: 1 1/2" = 1'-0"

Notes for Spiral Removal:

1. Contractor shall cut spiral shear developers as close to flange as possible. Burning off spirals from flange will not be allowed.
2. The studs will not be measured for payment. All costs shall be incidental to the concrete removal item.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 7/26/79	
REVISIONS	
SHA	FHWA
12-12-83	2-23-84
10-13-87	12-1-87
10-25-90	
5-18-93	

FHWA APPROVAL
DATE: 12-12-79

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

DETAIL OF ADDITIONAL REINFORCEMENT
AT EXISTING SHEAR DEVELOPERS
AND SPIRAL REMOVAL

STANDARD NO. BR-SS(6.10)-79-76

SHEET 1 OF 1

SUPER CONCRETE WORK

NOTES

- Design:
1. Latest A.A.S.H.T.O. Standard Specifications for Highway Bridges.
 2. $f'_C = 4500$ p.s.i., $f_C = 0.3 f'_C = 1350$ p.s.i.,
 $f_S = 24,000$ p.s.i.
 3. Design includes provision for 2" future wearing surface.
- General:
1. Transverse bars shall be placed normal to \perp stringers, except in case of curved stringers. When stringers are curved transverse bars shall be placed radially.
 2. When skew angles are greater than 60° then Contractor may use either Reinforcing Steel Pattern No. 1 or No. 2 throughout bridge.
 3. When the effective span is less than 5'-9", all bars shall be straight top and bottom. No truss bars are to be used.

APPROVAL	
<i>E. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVEL. DATE: 12/4/79	
REVISIONS	
SHA	FHWA
10-4-82	6-8-90
3-1-84	6-8-90
11-18-87	6-8-90
10-12-90	.

FHWA APPROVAL	11-18-87	6-8-90
DATE: 6-8-90	10-12-90	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

BRIDGE DECK SLAB
GENERAL NOTES AND BAR SPACING

STANDARD NO. BR-SS(6.11)-79-90

SHEET 1 OF 2

SUPER-CONCRETE WORK

NOTES

- Design:
1. Latest AASHTO LRFD Bridge Design Specifications.
 2. $f'_c = 4500$ p.s.i., $f_c = 0.3 f'_c = 1350$ p.s.i.,
 $f_s = 24,000$ p.s.i., $f_y = 60,000$ p.s.i.
 3. Design includes provision for 2" future wearing surface.
- General:
1. Transverse bars shall be placed normal to ϕ stringers, except in case of curved stringers. When stringers are curved transverse bars shall be placed radially.
 2. When skew angles are greater than 60° then Contractor may use either Reinforcing Steel Pattern No. 1 or No. 2 throughout bridge.
 3. When the effective span is less than 5'-9", all bars shall be straight top and bottom. No truss bars are to be used.
 4. Typical sections shall include a minimum of three stringers and have a width of not less than 14.0' between centerlines of exterior stringers.
 5. Overhangs shall be at least 21" but shall not exceed the smaller of 0.625 times the stringer spacing and 6.0'.
 6. Reinforcing in the slab overhangs shall be designed in accordance with AASHTO.

APPROVAL	
<i>L. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 12/4/79	
REVISIONS	
SHA	FHWA
3-1-84	6-8-90
11-18-87	6-8-90
10-12-90	.
10-9-07	.

FHWA APPROVAL
DATE: 6-8-90

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


BRIDGE DECK SLAB
GENERAL NOTES AND BAR SPACING

STANDARD NO. BR-SS(6.11)-79-90(L)


SHEET 1 OF 2



SUPER-CONCRETE WORK




REINFORCING STEEL PATTERN NO.1




REINFORCING STEEL PATTERN NO.2

1. The Contractor has the option of using Reinforcing steel Pattern No.1 or No.2 in the unhatched portions of the decks shown below.
2. The Contractor shall use only Reinforcing Steel Pattern No.1 in the hatched portions of the decks shown below.



TRANSVERSE BAR SPACING FOR SPANS
WITH SKEW ANGLES LESS THAN 60°

Scale: 1"=1'-0"




SKEW ANGLE
Scale: None


APPROVAL		
<i>L.S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVEL.		
DATE: 12/4/79		
REVISIONS		
SHA	FHWA	
10-4-82	6-8-90	
3-1-84	6-8-90	
11-18-87	6-8-90	
9-25-89	6-8-90	

STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION OFFICE OF BRIDGE DEVELOPMENT		
BRIDGE DECK SLAB GENERAL NOTES AND BAR SPACING		
STANDARD NO. BR-SS(6.11)-79-90		SHEET 2 OF 2

SUPER-CONCRETE WORK




REINFORCING STEEL PATTERN NO.1




REINFORCING STEEL PATTERN NO.2

1. The Contractor has the option of using Reinforcing steel Pattern No.1 or No.2 in the unhatched portions of the decks shown below.
2. The Contractor shall use only Reinforcing Steel Pattern No.1 in the hatched portions of the decks shown below.



TRANSVERSE BAR SPACING FOR SPANS
WITH SKEW ANGLES LESS THAN 60°

Scale: 1"=1'-0"



SKEW ANGLE
Scale: None

APPROVAL	
<i>L.S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 12/4/79	
REVISIONS	
SHA	FHWA
3-1-84	6-8-90
11-18-87	6-8-90
9-25-89	6-8-90
10-9-07	

FHWA APPROVAL
DATE: 6-8-90


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

BRIDGE DECK SLAB
GENERAL NOTES AND BAR SPACING

STANDARD NO. BR-SS(6.11)-79-90(L)


SHEET 2 OF 2





HS20 TYPE I SLAB
5'-9" TO 6'-0" EFFECTIVE SPAN
 Scale: 1/2"=1'-0"

Note:
 For effective spans less than 5'-9" see Note 3 on Std. No. BR-SS(6.11)-79-90.



HS20 TYPE II SLAB
GREATER THAN 6'-0" TO 6'-3" EFFECTIVE SPAN
 Scale: 1/2"=1'-0"



Note:
 Slanted lettering indicates notes "For Office Use Only".

- Note:
1. All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
 2. Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
 3. All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
 4. On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus ϕ . See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

APPROVAL	
<i>L.S. Friedman</i> DIRECTOR	OFFICE OF BRIDGE DEVEL.
DATE: 12/4/79	
REVISIONS	
SHA	FHWA
1-5-88	6-8-90
9-20-89	6-8-90
FHWA APPROVAL	3-22-00
DATE: 6-8-90	1-22-01

STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION OFFICE OF BRIDGE DEVELOPMENT TYPE I AND II BRIDGE DECK SLABS HS20 LOADING	STANDARD NO. BR-SS(6.12)-79-91	SHEET <u>1</u> OF <u>1</u>
---	--------------------------------	----------------------------

SUPER CONCRETE WORK



Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

Note:


Slanted lettering indicates notes "For Office Use Only".

APPROVAL	
<i>E.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 12/4/79	
REVISIONS	
SHA	FHWA
1-5-88	6-8-90
9-20-89	6-8-90
FHWA APPROVAL	3-22-00
DATE: 6-8-90	1-22-01

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT
 TYPE III AND IV
 BRIDGE DECK SLABS
 HS20 LOADING

STANDARD NO. BR-SS(6.13)-79-92

SHEET 1 OF 1



Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus \bigcirc . See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

FWHA APPROVAL
DATE: 6-8-90

APPROVAL	
<i>R. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 12/4/79	
REVISIONS	
SHA	FWHA
1-5-88	6-8-90
9-20-89	6-8-90
3-22-00	
1-22-01	



STANDARD NO. BR-SS(6.14)-79-93

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE V AND VI
BRIDGE DECK SLABS
HS20 LOADING

SHEET 1 OF 1

Note:

Slanted lettering indicates notes
"For Office Use Only".



Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

FHWA APPROVAL
DATE: 6-8-90

APPROVAL	
<i>E.S. Fisher</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 12/4/79	
REVISIONS	
SHA	FHWA
4-21-81	6-8-90
9-20-89	6-8-90
3-22-00	
1-22-01	


STANDARD NO. BR-SS(6.15)-79-94

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE VII AND VIII
BRIDGE DECK SLABS
HS20 LOADING


SHEET 1 OF 1

Note:

Slanted lettering indicates notes
"For Office Use Only".



HS20 TYPE IX SLAB
GREATER THAN 8'-9" TO 9'-8" EFFECTIVE SPAN
 Scale: 3/8"=1'-0"



HS20 TYPE X SLAB
GREATER THAN 9'-8" TO 10'-0" EFFECTIVE SPAN
 Scale: 3/8"=1'-0"

Note:

1. All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
 2. Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
 3. All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
 4. On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O.
- See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

FHWA APPROVAL	
DATE: 6-8-90	1-22-01

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 12/4/79	
REVISIONS	
SHA	FHWA
4-21-81	6-8-90
9-20-89	6-8-90
3-22-00	
1-22-01	


STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

TYPE IX AND X
 BRIDGE DECK SLABS
 HS20 LOADING

STANDARD NO. BR-SS(6.16)-79-95

SHEET 1 OF 1

SUPER CONCRETE WORK



Note:

1. * Omit concrete haunch by dropping bottom of concrete slab to bottom of top flange on spans of 30'-0" or less c/c of bearings.

APPROVAL	
<i>E. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/15/79	
REVISIONS	
SHA	FHWA
3-3-93	.
.	.
FHWA APPROVAL	.
DATE: 12-12-79	.


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

CONCRETE HAUNCH DETAIL FOR
BRIDGE DECKS FORMED WITH TIMBER

STANDARD NO. BR-SS(6.17)-79-98

SHEET 1 OF 1

SUPER - CONCRETE WORK



Notes:

1. All #7 and #8 longitudinal bars shall be placed continuously in the barrier from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multi-span bridge.
2. All reinforcing steel epoxy coated.
3. Concrete deck reinforcing steel not shown.
4. Place 1/2" saw cut joints to match joint spacing of outside parapet.
5. All keys are nominal size.
6. No increase in any prices bid will be allowed for barrier modifications due to roadway slope.

42" MEDIAN TL-5 BRIDGE RAILING

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 4/28/80	
REVISIONS	
SHA	FHWA
10-31-90	
6-5-91	
FHWA APPROVAL	10-22-03
DATE:	11-26-07


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

42" F-SHAPE MEDIAN BARRIER
FOR BRIDGE WITH OPEN LONGITUDINAL JOINT

STANDARD NO. BR-SS(6.19)-03-104

SHEET 1 OF 1

SUPER CONCRETE WORK



SECTION
Scale : 3/4"=1'-0"

- * In order to insure a smooth and acceptable surface, 420.03.11 (Constr. joints) shall be strictly adhered to.
- ** Unless otherwise indicated on "Typical Cross Section".
- *** Slab Depth - 1"

Notes:

1. All longitudinal bars are #5 spaced as shown and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multi-span bridge.
2. All keys are nominal size.
3. Portions of normal longitudinal deck steel and truss bars are not shown.
4. All reinforcing steel to be epoxy coated.

SIDEWALK WITH STRAIGHT BACK


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 5/15/80	
REVISIONS	
SHA	FHWA
1-22-01	.
10-22-03	.
11-18-05	.
11-26-07	.

FHWA APPROVAL
DATE: 7-29-80


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
LEVEL OR LOW SIDE OF CROWN
(OR SUPERELEVATED) SECTION OF
SIDEWALK AND PARAPET WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.21)-03-106

SHEET 1 OF 2



SECTION A
 (WHEN BOTTOM OF OVERHANG IS LOWER
 THAN BOTTOM OF TOP FLANGE)
 Scale: $\frac{3}{4}" = 1'-0"$



SECTION B
 (WHEN BOTTOM OF OVERHANG IS HIGHER
 THAN BOTTOM OF TOP FLANGE)
 Scale: $\frac{3}{4}" = 1'-0"$

* * Unless otherwise indicated on
 "Typical Cross Section".

Note:
 For all details not shown see
 sheet 1 of 2.

SIDEWALK WITH STRAIGHT BACK


APPROVAL	
<i>E.S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 7/2/98	
REVISIONS	
SHA	FHWA
10-22-03	.
11-18-05	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

HIGH SIDE OF CROWN (OR SUPERELEVATED) SECTION
 OF SIDEWALK AND PARAPET WITH STRAIGHT BACK


STANDARD NO. BR-SS(6.21)-03-106

SHEET 2 OF 2



ELEVATION AT INTERIOR BEAM

Scale: $\frac{1}{2}''=1'-0''$



ELEVATION AT EXTERIOR BEAM

Scale: $\frac{1}{2}''=1'-0''$

Note:

1. For Section B-B, see Standard No. BR-SS(8.12)-85-170.
2. * Longest leg of angle shall be increased as necessary so that angle exceeds stiffener width by at least $\frac{1}{2}''$. In lieu of the seat angle a $\frac{3}{4}''$ plate may be used. The plate shall be a minimum of 6'' wide and shall exceed stiffener width by at least $\frac{1}{2}''$.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 10/15/80	
REVISIONS	
SHA	FHWA
2-19-92	.
2-14-00	.
1-22-01	.
10-22-03	.


FHWA APPROVAL
DATE: 6-8-90

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

CONCRETE DIAPHRAGMS AT PIERS (WITH
EXPANSION JOINTS) AND AT ALL ABUTMENTS

STANDARD NO. BR-SS(6.22)-80-120

SHEET 1 OF 2



SECTION A-A

Scale: None

* Measured \perp to ϕ of Bearing.
 ** Measured \perp to ϕ of Bearing at
 Edge of Bearing Stiffener.

Span = S	Depth of Diaphragm = d	Re-bars "A"	Re-bars "B"	Ties "C"
Up to 8'	1'-11"	3-#7's	3-#7's	#5 @ 9" Maximum Spacing Place \perp to ϕ Bearing
over 8' to 11'	1'-11"	3-#8's	3-#8's	
over 11' to 14'	2'-0"	3-#8's	3-#8's	
over 14' to 16'	2'-1"	3-#9's	3-#9's	

Note:

1. Studs and anchors for seal retainer angle, not shown.
2. All reinforcing steel sizes and spacings based on ASTM A-615, Grade 60 $f_y = 60$ ksi.
3. For Section B-B, see Standard No. BR-SS(8.12)-85-170.

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 10/15/80	
REVISIONS	
SHA	FHWA
2-14-00	.
1-22-01	.
10-9-07	.
7-18-94	.




FHWA APPROVAL
 DATE: 6-8-90

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

CONCRETE DIAPHRAGMS AT PIERS (WITH
 EXPANSION JOINTS) AND AT ALL ABUTMENTS

STANDARD NO. BR-SS(6.22)-80-120

SHEET 2 OF 2



Notes:

1. See appropriate lap charts for Case I and Case 2 splice dimensions.
2. See Std. No. BR-SS(6.42)-95-311 for Longitudinal and Additional Top Bar over Pier lap length notes.
3. Min. Constr. Gap dim. = Case I Lap + 1'.
4. See Contract Drawing for construction gap location.

FHWA APPROVAL
DATE: 10-5-83

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR OFFICE OF BRIDGE DEVEL.
DATE: 10/3/83	
REVISIONS	
SHA	FHWA
3-9-89	6-8-90
2-19-92	.
11-15-95	.
1-22-01	.


STANDARD NO. BR-SS(6.23)-83-149

**STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT**

**SPlicing OF BRIDGE DECK SLAB
TRUSS BARS DURING STAGE CONSTRUCTION
LAP SPLICE ALTERNATIVES**

SHEET 1 OF 1

SUPER CONCRETE WORK



SECTION

Scale: 3/4" : 1'-0"

Notes:

- All #7 and #8 longitudinal bars shall be placed continuously in the barrier from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge.
- All reinforcement bars shall be epoxy coated.
- The Contractor has the option of substituting cast-in-place epoxy coated open coil inserts with threaded holes for the bars shown. The inserts in the back face of the parapet shall have a minimum working load tension strength of 6000 lb. and a minimum length of 4 1/2". The inserts in the front face shall have a minimum working load tension strength of 8000 lb. and a minimum length of 5 1/2". The cost of epoxy coated inserts shall be included in the pertinent Superstructure Concrete item.
- Concrete deck reinforcing steel not shown.
- Place 1/2" saw cut joints to match joint spacing of outside parapet.
- No increase in any prices bid will be allowed for barrier modifications due to roadway slope or maintenance of traffic.

* Slab depth minus 1".

** For high side of crown or superelevation, otherwise this is a vertical line that all dimensions are measured from.

*** These dimensions can change if superelevation affects barrier face alignment.

**** Dowel may replace vertical by being extended full height.

42" MEDIAN

APPROVAL

L. S. Friedman DIRECTOR
OFFICE OF BRIDGE DEVEL.

DATE: 11/2/83

REVISIONS

SHA	FHWA
8-17-90	-
10-26-90	-
7-2-93	-
10-22-03	-

FHWA APPROVAL


DATE: 12-9-83

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

42" F-SHAPE MEDIAN BARRIER FOR BRIDGE
WITH LONGITUDINAL JOINT WHERE TRAFFIC WILL USE
AREA PRIOR TO PLACING BARRIER


STANDARD NO. BR-SS(6.24)-03-156

SHEET 1 OF 1



SUPER CONCRETE WORK


SHEET 1 OF 2



SECTION A

(WHEN BOTTOM OF OVERHANG IS LOWER
THAN BOTTOM OF TOP FLANGE)

Scale: $\frac{3}{4}" = 1'-0"$



SECTION B

(WHEN BOTTOM OF OVERHANG IS HIGHER
THAN BOTTOM OF TOP FLANGE)

Scale: $\frac{3}{4}" = 1'-0"$

* * Unless otherwise indicated on
"Typical Cross Section".

Note:
For all details not shown see
sheet 1 of 2.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 5/11/90	
REVISIONS	
SHA	FHWA
7-6-92	.
9-24-96	.
10-22-03	.
11-18-05	.

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

HIGH SIDE OF CROWN (OR SUPERELEVATED)
SECTION OF SIDEWALK AND PARAPET WITH DIAMOND BACK

STANDARD NO. BR-SS(6.26)-03-161

SHEET 2 OF 2

SUPER CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal slab steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 4" ϕ conduit, full length of bridge.

#5 \angle top and bottom epoxy coated.

ϕ Parapet control joint.

#5 \angle Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

#5 \angle Ties, epoxy coated, @ 12" c/c See Sheet 2 of 2.

5'-7" Min.

ϕ Parapet control joint.

2'-3/4"

See "Note A" 1'-10"

1'-1/2"

1'-1/2"

1'-10"

A/2

A/2

A (Minimum 6'-5")

Note:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations).

PLAN

Scale: 1/2"=1'-0"

10" x 10" x 8" or 10" x 12" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

ϕ 4" ϕ conduit

#5 \angle Ties

#5 \angle Ties See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

Note:
Normal slab reinforcing steel not shown.
Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts.
Maximum height of pole for this detail is 40'.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/8/84	
REVISIONS	
SHA	FHWA
5-26-92	.
1-8-93	.
9-24-96	.
1-9-08	.

FHWA APPROVAL
DATE: 3-19-85


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR
BRIDGE MOUNTED LIGHT POST
ON SIDEWALK WITH SPECIAL PARAPET


STANDARD NO. BR-SS(6.27)-84-166

SHEET 1 OF 2

SUPER-CONCRETE WORK



Note:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations).



Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts.
Maximum height of pole for this detail is 40'.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/8/84	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
11-26-07	.
1-9-08	.

FHWA APPROVAL
DATE: 3-19-85

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR
BRIDGE MOUNTED LIGHT POST
ON SIDEWALK WITH SPECIAL PARAPET



STANDARD NO. BR-SS(6.27)-84-166(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B
Scale: 1/2" = 1'-0"

OTHER RELATED STANDARDS
REBAR-PL(3.03)-91-263
REBAR-BD(3.04)-91-257


APPROVAL	
<i>L. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVEL.	
DATE: 11/8/84	
REVISIONS	
SHA	FHWA
2-14-92	.
2-19-93	.
9-24-96	.
FHWA APPROVAL	DATE: 3-19-85
8-7-98	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SUPPORT BRACKET FOR
BRIDGE MOUNTED LIGHT POST
ON SIDEWALK WITH SPECIAL PARAPET

STANDARD NO. BR-SS(6.27)-84-166

SHEET 2 OF 2

SUPER-CONCRETE WORK



SECTION B-B
Scale: 1/2" = 1'-0"

OTHER RELATED STANDARDS
REBAR-PL(3.03)-91-263
REBAR-BD(3.04)-91-257

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/8/84	
REVISIONS	
SHA	FHWA
2-19-93	.
9-24-96	.
8-7-98	.
11-26-07	.

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SUPPORT BRACKET FOR
BRIDGE MOUNTED LIGHT POST
ON SIDEWALK WITH SPECIAL PARAPET



STANDARD NO. BR-SS(6.27)-84-166(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal deck steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 4" ϕ conduit, full length of bridge.

#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \sqsubset Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

Parapet

ϕ Parapet control joint.

ϕ Bracket

See "Note A"

1'-10"

1'-1/2"

1'-1/2"

1'-10"

A/2

A/2

A (Minimum 6'-5") See Note B

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Normal deck reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN

Scale: 1/2"=1'-0"

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

ϕ 4" ϕ conduit

#5 \sqsubset Ties

#5 \sqsubset Ties. See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

34" DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 4/8/84	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
FHWA APPROVAL	6-1-05
DATE: 3-19-85	1-9-08

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-167A

SHEET 1 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to deck overhang steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 4" ϕ conduit, full length of bridge.

#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \sqsubset Ties

Spacing to match that of deck overhang steel (Varies 5" to 7"). Bars to be placed between deck overhang steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

Parapet

ϕ Parapet control joint.

ϕ Bracket

See "Note A"

1'-10"

1'-1/2"

1'-1/2"

1'-10"

A/2

A/2

A (Minimum 6'-5") See Note B

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Deck overhang reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN

Scale: 1/2"=1'-0"

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

ϕ 4" ϕ conduit

#5 \sqsubset Ties

#5 \sqsubset Ties. See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

34" DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 4/8/84	
REVISIONS	
SHA	FHWA
9-24-96	.
6-1-05	.
11-26-07	.
1-9-08	.

FHWA APPROVAL
DATE: 3-19-85

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-167A(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B
Scale: 3/4"=1'-0"

Note:
All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.25)-03-159A.

Note C:
The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

34" DIAMOND BACK

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 11/8/84	
REVISIONS	
SHA	FHWA
8-5-92	.
1-8-93	.
9-24-96	.
FHWA APPROVAL	DATE: 3-19-85
6-1-05	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-167A

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B
Scale: 3/4"=1'-0"

Note:
All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.25)-03-159A.

Note C:
The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

34" DIAMOND BACK

APPROVAL	
<i>L. S. Friedman</i> DIRECTOR	OFFICE OF BRIDGE DEVEL.
DATE: 11/8/84	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
6-1-05	.
11-26-07	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT



SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-167A(L)

SHEET 2 OF 2

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal deck steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 4" ϕ conduit, full length of bridge.

#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \sqsubset Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

Parapet

ϕ Parapet control joint.

ϕ Bracket

See "Note A"

1'-10" 1'-1 1/2" 1'-1 1/2" 1'-10"

A/2

A

(Minimum 6'-5") See Note B

PLAN

Scale: 1/2"=1'-0"

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Normal deck reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

ϕ 4" ϕ conduit

#5 \sqsubset Ties

#5 \sqsubset Ties. See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

42" DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-167B

SHEET 1 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to deck overhang steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 4" ϕ conduit, full length of bridge.

#5 \hook top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \hook Ties

Spacing to match that of deck overhang steel (Varies 5" to 7"). Bars to be placed between deck overhang steel.

8-#5 \hook Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

Parapet

ϕ Parapet control joint.

ϕ Bracket

See "Note A"

1'-10"

A/2

A (Minimum 6'-5") See Note B

1'-10"

1'-1 1/2"

1'-1 1/2"

1'-10"

3" min.

3" min.

2'-3 3/4"

8"

5'-7" Min.

1'-0"

BA

PLAN

Scale: 1/2"=1'-0"

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Deck overhang reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

#5 \hook Ties

#5 \hook Ties. See Sheet 2 of 2.

ϕ 4" ϕ conduit

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction box with cover. Provide holes in box for 4" ϕ conduit.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

42" DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
11-26-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET WITH DIAMOND BACK



STANDARD NO. BR-SS(6.28)-05-167B(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B
Scale: 3/4"=1'-0"

Note:
All #7 and #8 bars shall be placed
continuously in the parapet from
expansion opening to expansion opening
in a simple span bridge and expansion
opening to centerline of pier in a
multispan bridge. Refer to
BR-SS(6.25)-03-I59B.

Note C:
The constr. jt. between the F-shape
parapet and the deck may vary
slightly from the joint indicated.
For exact details and location of the
joint see "Superstructure"
Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
.	.


42" DIAMOND BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-I67B

SHEET 2 OF 2



SECTION B-B
Scale: 3/4"=1'-0"

Note:
All #7 and #8 bars shall be placed
continuously in the parapet from
expansion opening to expansion opening
in a simple span bridge and expansion
opening to centerline of pier in a
multispan bridge. Refer to
BR-SS(6.25)-03-159B.

Note C:
The constr. jt. between the F-shape
parapet and the deck may vary
slightly from the joint indicated.
For exact details and location of the
joint see "Superstructure"
Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
11-26-07	

42" DIAMOND BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.28)-05-167B(L)


SHEET 2 OF 2

SUPER-CONCRETE WORK

* - See appropriate Lap Chart.



SECTION
Scale: $\frac{3}{4}'' = 1'-0''$



SECTION B-B
Scale: $\frac{3}{4}'' = 1'-0''$

Notes:

1. Normal deck reinforcing not shown for clarity.
2. Wood forms may be used in the area of the scupper as approved by the Engineer.
3. Type I scupper shown.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 8/7/98	
REVISIONS	
SHA	FHWA
10-22-03	


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
BRIDGE DECK REINFORCEMENT
PATTERN IN SCUPPER AREA FOR
SCUPPER TYPES I, IA, IV AND V AT SIDEWALK

STANDARD NO. BR-SS(6.29)-85-171

SHEET 1 OF 1


SUPER CONCRETE WORK



Bridge # _____	Description: _____		
Location	L' (Back Stationing Span)	L (Ahead Stationing Span)	Bar Size *
Pier _____			
Pier _____			
Pier _____			
Pier _____			
Pier _____			
Pier _____			

* All bars to be #5 unless otherwise noted in this column.

Note:
1. If additional longitudinal reinforcing in pour requires splicing, then the reinforcing shall be spliced as per Splice Location Layout.



APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/31/88	
REVISIONS	
SHA	FHWA
7-6-88	6-8-90
3-16-89	6-8-90
FHWA APPROVAL	
DATE: 6-8-90	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
ADDITIONAL LONGITUDINAL
REINFORCING IN TOP OF CONTINUOUS
DECK SLABS OVER PIERS

STANDARD NO. BR-SS(6.30)-88-195


SHEET 1 OF 1

SUPER CONCRETE WORK

GENERAL NOTES


1. Longitudinal deck reinforcing steel not shown.
2. Existing slab shown dashed.
3. Splicer bars and normal transverse reinforcing steel to be placed in same horizontal plane.
4. These splice bars will not be measured for payment, but all costs thereof shall be included in the Contract lump sum price for the pertinent Epoxy Coated Reinforcing Steel items.
- 5a. Root diameter of threaded portion of splicer bar must be equal to nominal diameter of designed bar. Increasing bar diameter to next size is permissible to maintain this requirement.
- 5b. In no case shall the splicer rebar coupler flange encroach into the slab top or bottom concrete cover. Either no flange or clipping the top and bottom edges of the flange prior to application of the epoxy coating in the shop is permissible. (See details below)
6. *FOR OFFICE USE ONLY*
This detail is intended for use on stage construction where the gap between stages of construction does not accommodate the minimum bar lap lengths.

Certification: The steel manufacturer shall furnish certification with actual test results for each heat of steel, showing that the material conforms to these Specifications.




SECTION A-A

Scale: $\frac{1}{2}'' = 1'-0''$



FRONT VIEW ROUND FLANGE

Scale: None



FRONT VIEW SQUARE FLANGE

Scale: None

APPROVAL	
DIRECTOR OFFICE OF BRIDGE DEVEL.	
DATE: 7/20/88	
REVISIONS	
SHA	FHWA
2-28-89	6-8-90
11-15-95	.
9-24-96	.
FHWA APPROVAL	.
DATE: 6-8-90	.


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SPlicing OF BRIDGE DECK SLAB REINFORCING
STEEL DURING STAGE CONSTRUCTION
(NO AREA AVAILABLE FOR LAPPING)

STANDARD NO. BR-SS(6.31)-88-199

SHEET 1 OF 4


SUPER CONCRETE WORK



SECTION

OPTION I

Scale: 1/2" = 1'-0"



SECTION

OPTION II

Scale: 1/2" = 1'-0"

Other Related Standards
BR-SS(6.42)-95-311

Notes:

1. For General Notes see Sht. No. 1 of 4.
2. Work with sheets 3 and 4 of 4.

FHWA APPROVAL
DATE: 6-8-90


APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR OFFICE OF BRIDGE DEVEL.
DATE: 7/20/88	
REVISIONS	
SHA	FHWA
7-31-91	.
11-15-95	.
.	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SPlicing OF BRIDGE DECK SLAB
TRUSS BARS DURING STAGE CONSTRUCTION
COUPLER BAR SPLICE ALTERNATIVES

STANDARD NO. BR-SS(6.31)-88-199


SHEET 2 OF 4

SUPER CONCRETE WORK



SECTION
OPTION III

Scale: 1/2" = 1'-0"



SECTION
OPTION IV

Scale: 1/2" = 1'-0"

Other Related Standards
BR-SS(6.42)-95-311

Notes:

1. Work with sheets 2 and 4 of 4.
2. For General Notes see Sht. No. 1 of 4.

FHWA APPROVAL
DATE: 6-8-90


APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR OFFICE OF BRIDGE DEVELOPMENT
DATE: 7/20/88	
REVISIONS	
SHA	FHWA
8-14-89	6-8-90
7-31-91	.
11-15-95	.
.	.

STANDARD NO. BR-SS(6.31)-88-199


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SPlicing OF BRIDGE DECK SLAB
TRUSS BARS DURING STAGE CONSTRUCTION
COUPLER BAR SPLICE ALTERNATIVES

SHEET 3 OF 4

SUPER CONCRETE WORK



SECTION
OPTION V
Scale: 1/2" = 1'-0"



SECTION
OPTION VI
Scale: 1/2" = 1'-0"

* Constr. Gap dim. \geq Case 2 Lap dim. + 1"
Constr. Gap dim. $<$ Case 1 Lap dim. + 1"

Other Related Standards
BR-SS(6.42)-95-311

Notes:

1. Work with sheets 2 and 3 of 4.
2. For General Notes see Sht. No. 1 of 4.

FHWA APPROVAL
DATE:


APPROVAL	
<i>R. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 11/25/95	
REVISIONS	
SHA	FHWA
.	.
.	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SPlicing OF BRIDGE DECK SLAB
TRUSS BARS DURING STAGE CONSTRUCTION
COUPLER BAR SPLICE ALTERNATIVES

STANDARD NO. BR-SS(6.31)-88-199


SHEET 4 OF 4

SUPER CONCRETE WORK



Note:

For effective spans less than 5'-9" see Note 3 on Std. No. BR-SS(6.11)-79-90.



HS25 TYPE XXII SLAB

GREATER THAN 6'-0" TO 6'-6" EFFECTIVE SPAN

Scale: 1/2"=1'-0"

- Note:
- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
 - Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
 - All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
 - On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.



Note:

Slanted lettering indicates notes "For Office Use Only".

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 9/20/89	
REVISIONS	
SHA	FHWA
3-22-00	
1-22-01	
FHWA APPROVAL	
DATE: 12-27-89	

<p>STATE OF MARYLAND</p> <p>DEPARTMENT OF TRANSPORTATION</p> <p>STATE HIGHWAY ADMINISTRATION</p> <p>OFFICE OF BRIDGE DEVELOPMENT</p> <p>TYPE XXI AND XXII</p> <p>BRIDGE DECK SLABS</p> <p>HS25 LOADING</p>	<p>STANDARD NO. BR-SS(6.32)-89-209</p> <p>SHEET <u>1</u> OF <u>1</u></p>
--	--

SUPER CONCRETE WORK



Note:

1. All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
2. Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
3. All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
4. On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

Note:


Slanted lettering indicates notes
 "For Office Use Only".

APPROVAL	
<i>E.S. Friedman</i> DIRECTOR	OFFICE OF BRIDGE DEVEL.
DATE: 9/20/89	
REVISIONS	
SHA	FHWA
3-20-00	
1-22-01	
FHWA APPROVAL	
DATE: 12-27-89	


STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT
 TYPE XXIII AND XXIV
 BRIDGE DECK SLABS
 HS25 LOADING

STANDARD NO. BR-SS(6.33)-89-210

SHEET 1 OF 1



HS25 TYPE XXV SLAB
GREATER THAN 7'-6" TO 7'-9" EFFECTIVE SPAN
 Scale: 1/2"=1'-0"



HS25 TYPE XXVI SLAB
GREATER THAN 7'-9" TO 8'-3" EFFECTIVE SPAN
 Scale: 1/2"=1'-0"

Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

Note:


Slanted lettering indicates notes
 "For Office Use Only".

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 9/20/89	
REVISIONS	
SHA	FHWA
12-8-92	
3-20-00	
1-22-01	
FHWA APPROVAL	
DATE: 12-27-89	


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE XXV AND XXVI
BRIDGE DECK SLABS
HS25 LOADING

STANDARD NO. BR-SS(6.34)-89-211

SHEET 1 OF 1



HS25 TYPE XXVII SLAB
GREATER THAN 8'-3" TO 8'-9" EFFECTIVE SPAN
 Scale: 3/8"=1'-0"



HS25 TYPE XXVIII SLAB
GREATER THAN 8'-9" TO 9'-8" EFFECTIVE SPAN
 Scale: 3/8"=1'-0"

Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus \bigcirc . See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

Note:


Slanted lettering indicates notes
"For Office Use Only".

APPROVAL	
<i>E.S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 9/20/89	
REVISIONS	
SHA	FHWA
6-8-93	
3-20-00	
1-22-01	
FHWA APPROVAL	
DATE: 12-27-89	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE XXVII AND XXVIII
BRIDGE DECK SLABS
HS25 LOADING

STANDARD NO. BR-SS(6.35)-89-212

SHEET 1 OF 1



HS25 TYPE XXIX SLAB
GREATER THAN 9'-8" TO 10'-0" EFFECTIVE SPAN
Scale: 3/8"=1'-0"

Note:

1. All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
2. Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90).
3. All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
4. On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.

Note:

Slanted lettering indicates notes
"For Office Use Only".

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 9/20/89	
REVISIONS	
SHA	FHWA
3-20-00	.
1-22-01	.
FHWA APPROVAL	.
DATE: 12-27-89	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

TYPE XXIX BRIDGE DECK SLAB
HS25 LOADING


STANDARD NO. BR-SS(6.36)-89-213

SHEET 1 OF 1

SUPER CONCRETE WORK

6" x 6" x 8" galvanized
cast iron, galvanized steel
or fiberglass U.L. listed
junction boxes with covers.
Provide holes in box for
3" ϕ conduit.

Note: Details shown are for single rail;
double rail and fencing details are similar.
On bridges with no fencing or railing see
General Plan and Elevation for parapet
control joint spacing.



ELEVATION
Scale: $\frac{3}{8}" = 1'-0"$

Note: For Section A-A and B-B
see sheets 2 & 3 of 4.
For View D-D see sheet
2 and 3 of 4.
For Sections A-A and B-B
at centerline of pier on
multi-span continuous
bridges, see sheet 4 of 4.

- Notes:
- The conduits and junction boxes are to be placed only when indicated in the Superstructure "Typical Section." If ϕ to ϕ of end junction boxes exceed 200', then additional junction boxes shall be placed in parapet, between control joints, so that the maximum distance between boxes is 200'. Junction boxes for light standards, may be utilized. All junction boxes to have $\frac{1}{2}" \phi$ drain at drain at low point of box.
 - Conduit may be either PVC or galvanized pipe.

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/27/91	
REVISIONS	
SHA	FHWA
6-1-05	.
10-13-06	.
1-9-08	.
4-16-08	.




FHWA APPROVAL
DATE: .

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
PARAPET CONTROL JOINT AND DUAL CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK

STANDARD NO. BR-SS(6.37)-05-247A


SHEET 1 OF 4

SUPER-CONCRETE WORK




SECTION B-B

Scale: $\frac{3}{8}'' = 1'-0''$




SECTION A-A

Scale: None



VIEW D-D - F-SHAPE PARAPET

Scale: $\frac{3}{8}'' = 1'-0''$



SECTION C-C

Scale: None

Notes:

1. Place saw cut joint at center of every rail panel.
2. Parapet is placed continuously.
3. Saw cut control joint to be sawed same day as concrete is poured.
4. Fencing and railing not shown.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
12-1-93	.
9-24-96	.
1-22-01	.
6-1-05	.


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND DUAL CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK


STANDARD NO. BR-SS(6.37)-05-247A

SHEET 2 OF 4




SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$

$\frac{1}{2}''\phi$ drain (typ.). Connect drain to low point of junction box. For intermediate junction boxes outlet drain thru bottom of superstructure.




VIEW D-D - PARAPET WITH SIDEWALK

Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



SECTION C-C
Scale: None

Notes:

1. Place saw cut joint at center of every rail panel.
2. Parapet is placed continuously.
3. Saw cut joint to be sawed same day as concrete is poured.
4. Fencing and railing not shown.

APPROVAL	
<i>E. Schuman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/27/91	
REVISIONS	
SHA	FHWA
10-30-92	
12-1-93	
9-24-96	
6-1-05	


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
PARAPET CONTROL JOINT AND DUAL CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK


STANDARD NO. BR-SS(6.37)-05-247A

SHEET 3 OF 4


SUPER-CONCRETE WORK



SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



SECTION C-C
Scale: Full

Notes:

1. Place vertical paraffin joint, shown hatched, at centerline of pier on multi-span continuous bridges.
2. The placement of adjacent sections shall have a 40 hour delay between placements.
3. Railing and fencing not shown.

*In order to insure a smooth and acceptable surface, 420.03.11 (Construction Joints) will be strictly adhered to.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 12/1/93	
REVISIONS	
SHA	FHWA
9-24-96	
12-17-01	
6-1-05	
10-13-06	


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
PARAPET CONTROL JOINT AND DUAL CONDUIT
PLACEMENT WITH 34" F-SHAPE PARAPET AND
PARAPET WITH SIDEWALK

STANDARD NO. BR-SS(6.37)-05-247A

SHEET 4 OF 4

Note: Details shown are for single rail; double rail and fencing details are similar. On bridges with no fencing or railing see General Plan and Elevation for parapet control joint spacing.



Note: For Section A-A & B-B
see sheet 2 of 3.
For View D-D see sheet
2 of 3.
For Sections A-A and B-B
at centerline of pier on
multi-span continuous
bridges, see sheet
3 of 3.

1. The conduits and junction boxes are to be placed only when indicated in the Superstructure "Typical Section." If $\frac{1}{2}$ " to $\frac{3}{4}$ " of end junction boxes exceed 200', then additional junction boxes shall be placed in parapet, between control joints, so that the maximum distance between boxes is 200'. Junction boxes for light standards, may be utilized. All junction boxes to have $\frac{1}{2}$ " ϕ drain at drain at low point of box.
2. Conduit may be either PVC or galvanized pipe.

APPROVAL	
<u>E.S. Freedom</u> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-13-06	.
1-9-08	.
4-16-08	.
.	.




STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND DUAL CONDUIT PLACEMENT WITH 42" E-SHAPE PARAPET


STANDARD NO. BR-SS(6.37)-05-247B

SHEET 1 OF 3


SUPER-CONCRETE WORK




SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



VIEW D-D
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION C-C
Scale: None

- Notes:
1. Place saw cut joint at center of every rail panel.
 2. Parapet is placed continuously.
 3. Saw cut control joint to be sawed same day as concrete is poured.
 4. Fencing and railing not shown.

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
FHWA APPROVAL	
DATE:	




STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND DUAL CONDUIT
PLACEMENT WITH 42" F-SHAPE PARAPET


STANDARD NO. BR-SS(6.37)-05-247B

SHEET 2 OF 3


SUPER-CONCRETE WORK



SECTION B-B
Scale: $\frac{3}{8}'' = 1'-0''$



SECTION A-A
Scale: None



SECTION C-C
Scale: Full

*In order to insure a smooth and acceptable surface, 420.03.11 (Construction Joints) will be strictly adhered to.

Notes:

1. Place vertical paraffin joint, shown hatched, at centerline of pier on multi-span continuous bridges.
2. The placement of adjacent sections shall have a 40 hour delay between placements.
3. Railing and fencing not shown.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND DUAL CONDUIT
PLACEMENT WITH 42" F-SHAPE PARAPET


STANDARD NO. BR-SS(6.37)-05-247B

SHEET 3 OF 3



Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

PLAN
 Scale: 1/2" = 1'-0"



SECTION A-A
 Scale: 1/2" = 1'-0"

Note:
 Normal deck reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

34" STRAIGHT BACK

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
1-8-93	
9-24-96	
FHWA APPROVAL	6-1-05
DATE:	1-9-08


STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
 WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248A

SHEET 1 OF 2

SUPER-CONCRETE WORK




Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:
 Deck overhang reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN
 Scale: $\frac{1}{2}" = 1'-0"$



SECTION A-A
 Scale: $\frac{1}{2}" = 1'-0"$

For Section "B-B" see Sheet 2 of 2.

34" STRAIGHT BACK

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
9-24-96	
6-1-05	
10-9-07	
1-9-08	

FHWA APPROVAL
 DATE:

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
 WITH STRAIGHT BACK


STANDARD NO. BR-SS(6.38)-05-248A(L)

SHEET 1 OF 2



SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27A.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

34'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
8-7-98	.
6-1-05	.

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34'' F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248A

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27A.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

34'' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
9-24-96	.
8-7-98	.
6-1-05	.
10-9-07	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248A(L)

SHEET 2 OF 2




SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal deck steel. Hook one end.

Provide slip hole or drill and tap box for 1/4"φ conduit.


φ 3"φ conduits, full length of bridge.


#5  top and bottom epoxy coated.

φ Parapet control joint.

4-#5  Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

8-#5  Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.




Note B:
Station for light post support bracket shown on Plans is only approximate. φ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at φ of pier, eliminate the control joint at the φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:
Normal deck reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.


PLAN
Scale: 1/2"=1'-0"



SECTION A-A
Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

42" STRAIGHT BACK

APPROVAL	
	DIRECTOR OFFICE OF BRIDGE DEVEL.
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.

FHWA APPROVAL
DATE: .

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248B

SHEET 1 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to deck overhang steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 3" ϕ conduits, full length of bridge.


#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.

4-#5 \sqsubset Ties


Spacing to match that of deck overhang steel (Varies 5" to 7"). Bars to be placed between deck overhang steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.



PLAN
Scale: 1/2"=1'-0"

Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
Scale: 1/2"=1'-0"

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

42" STRAIGHT BACK

APPROVAL	
<i>E. Schuman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248B(L)

SHEET 1 OF 2



SUPER-CONCRETE WORK



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27B.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

42' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE:	


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248B

SHEET 2 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR "F-SHAPE" BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.02)-03-27B.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

42' STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	.
.	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT



SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH STRAIGHT BACK

STANDARD NO. BR-SS(6.38)-05-248B(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal deck steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 3" ϕ conduits, full length of bridge.

#5 \square top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \square Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

8-#5 \square Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

Parapet

ϕ Parapet control joint.

ϕ Bracket

See "Note A"

A (Minimum 6'-5") See Note B

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Normal deck reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN

Scale: 1/2"=1'-0"

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction boxes with cover. Provide holes in box for 3" ϕ conduit.

ϕ 3" ϕ conduits

#5 \square Ties

#5 \square Ties. See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

34" DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
6-1-05	.
1-9-08	.

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.40)-05-250A

SHEET 1 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to deck overhang steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 3" ϕ conduits, full length of bridge.

#5 \square top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \square Ties

8-#5 \square Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

ϕ Parapet control joint.

ϕ Bracket

See "Note A"

A (Minimum 6'-5") See Note B

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Deck overhang reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN
Scale: 1/2"=1'-0"

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction boxes with cover. Provide holes in box for 3" ϕ conduit.

ϕ 3" ϕ conduits

#5 \square Ties

#5 \square Ties. See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A
Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

34" DIAMOND BACK

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
9-24-96	.
6-1-05	.
10-9-07	.
1-9-08	.

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT



SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.40)-05-250A(L)

SHEET 1 OF 2

Technical drawing of a parapet detail showing reinforcement and drainage. The drawing includes the following dimensions and annotations:

- Horizontal dimensions: 1'-6", 1'-2", 1'-7 1/4".
- Vertical dimensions: 2'-0", 10", 1'-2", 7", 1/2".
- Reinforcement: 5-#5 ties, #5 bars at 8" c/c to alternate with 8-#5 bars at 8" c/c in place of normal parapet reinforcing, #5 bars top and bottom, 12-#9 bars.
- Drainage: 1/4" conduit, bend using 8" max. radius, 1/2" drains, Connect drain to low point of conduit, Connect drain to low point of junction box (typ.).
- Other annotations: Slope to match back face of parapet., Cap, See "Note C", Normal deck reinforcing not shown.

Scale: $\frac{3}{4}'' = 1' - 0''$

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

APPROVAL	
<u>E.S. Freedom</u> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
6-1-05	.
.	.

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

SHEET 2 OF 2

SUPER-CONCRETE WORK

Technical drawing of a parapet detail showing reinforcement and drainage. The drawing includes the following dimensions and annotations:

- Horizontal dimensions: 1'-6", 1'-2", 1'-7 1/4".
- Vertical dimensions: 2'-0", 10", 1'-2", 7", 1/2".
- Reinforcement: 5-#5 ties, #5 bars at 8" c/c to alternate with 8-#5 bars at 8" c/c in place of normal parapet reinforcing, #5 bars top and bottom, 12-#9 bars.
- Drainage: 1/4" conduit, bend using 8" max. radius, 1/2" drains, Connect drain to low point of conduit, Connect drain to low point of junction box (typ.).
- Other annotations: Slope to match back face of parapet., Cap, See "Note C", Normal deck reinforcing not shown.

Scale: $\frac{3}{4}'' = 1' - 0''$

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

APPROVAL	
<u>E.S. Freedom</u> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 3/26/91	
REVISIONS	
SHA	FHWA
1-8-93	.
9-24-96	.
6-1-05	.
10-9-07	.

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH DIAMOND BACK

SHEET 2 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal deck steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 3" ϕ conduits, full length of bridge.

#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \sqsubset Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

5'-7" Min.
8"
Parapet

ϕ Parapet control joint.

A

3" min.

3" min.

2'-3/4"

A

See "Note A"

1'-10"

1'-1 1/2"

1'-1 1/2"

1'-10"

A/2

A (Minimum 6'-5") See Note B

A/2

ϕ Bracket

PLAN

Scale: 1/2"=1'-0"

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Normal deck reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

1/2" ϕ Drain at low point of junction box.

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction boxes with cover. Provide holes in box for 3" ϕ conduit.

ϕ 3" ϕ conduits

#5 \sqsubset Ties

#5 \sqsubset Ties. See Sheet 2 of 2.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

42" DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.40)-05-250B

SHEET 1 OF 2

SUPER-CONCRETE WORK

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to deck overhang steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 3" ϕ conduits, full length of bridge.

#5 \sqsubset top and bottom epoxy coated.

ϕ Parapet control joint.

5-#5 \sqsubset Ties

Spacing to match that of deck overhang steel (Varies 5" to 7"). Bars to be placed between deck overhang steel.

8-#5 \sqsubset Ties, epoxy coated, @ 8" c/c See Sheet 2 of 2.

5'-7" Min.

Parapet

ϕ Parapet control joint.

2'-3/4"

A

See "Note A"

1'-10"

A/2

1'-1 1/2"

1'-1 1/2"

1'-10"

ϕ Bracket

A/2

A (Minimum 6'-5") See Note B

PLAN

Scale: 1/2"=1'-0"

Note B:

Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints. A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations). If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:

Deck overhang reinforcing steel not shown.

Note A:

Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

1/2" ϕ Drain at low point of junction box.

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction boxes with cover. Provide holes in box for 3" ϕ conduit.

ϕ 3" ϕ conduits

#5 \sqsubset Ties

#5 \sqsubset Ties. See Sheet 2 of 2.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

42" DIAMOND BACK

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	.
1-9-08	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH DIAMOND BACK



STANDARD NO. BR-SS(6.40)-05-250B(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B
Scale: 3/4"=1'-0"

Note:
All #7 and #8 bars shall be placed
continuously in the parapet from
expansion opening to expansion opening
in a simple span bridge and expansion
opening to centerline of pier in a
multispan bridge. Refer to
BR-SS(6.25)-03-159B.

Note C:
The constr. jt. between the F-shape
parapet and the deck may vary
slightly from the joint indicated.
For exact details and location of the
joint see "Superstructure"
Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
.	.


42" DIAMOND BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH DIAMOND BACK

STANDARD NO. BR-SS(6.40)-05-250B


SHEET 2 OF 2



- * Coat weld with epoxy touch up.
** See appropriate standard for rebar types and spacing pattern.

ELEVATION

Scale: $\frac{1}{2}" = 1'-0"$



ELEVATION-MULTISPAN AT PIER

Scale: $\frac{1}{2}" = 1'-0"$

34" OR 42" PARAPET OR MEDIAN

Note:

1. All longitudinal bars shall be placed continuously in the parapet/median barrier from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multi span bridge.

APPROVAL	
<i>E.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 2/17/94	
REVISIONS	
SHA	FHWA
10-22-03	

FHWA APPROVAL
DATE:


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

ADDITIONAL REINFORCING FOR SLIP FORMING
PARAPETS AND MEDIAN BARRIERS

STANDARD NO. BR-SS(6.4I)-94-297

SHEET 1 OF 1

SUPER - CONCRETE WORK




** This splice location can only be used if truss bottom leg dimension is greater than or equal to lap length.

No more than one splice may occur within every 3rd stringer or 3rd bay.

All bars must splice in the same plane (all in top of slab or all in bottom of slab).

SECTION
OPTIONAL TRANSVERSE TRUSS BAR SPLICE
Scale: None



Optional splices shown may not be used for decks 45'-0" or less in width.

SECTION
OPTIONAL TRANSVERSE STRAIGHT BAR SPLICE
Scale: None

Notes:

1. See sheet 2 of 2 for longitudinal steel splice details.
2. Refer to pertinent bar lap charts for definition of cases and lap lengths.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/14/95	
REVISIONS	
SHA	FHWA
4-21-09	.
.	.
.	.
.	.

FHWA APPROVAL
DATE: .


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

BRIDGE DECK SLAB
SPLICE LOCATIONS


STANDARD NO. BR-SS(6.42)-95-311

SHEET 1 OF 2

SUPER CONCRETE WORK




SECTION
Scale: None



PLAN
TOP LONGITUDINAL SPLICES
Scale: None

Notes:

1. Top normal longitudinal splice length shall not be increased in area of additional longitudinal bars over pier.
2. Category of bottom longitudinal splice based on spacing of bars in bottom of truss.



FHWA APPROVAL
DATE:

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR OFFICE OF BRIDGE DEVEL.
DATE: 11/14/95	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

BRIDGE DECK SLAB
SPLICE LOCATIONS


STANDARD NO. BR-SS(6.42)-95-311

SHEET 2 OF 2

SUPER CONCRETE WORK



SECTION VIEW FOR 1st POUR
Scale: 1/2" = 1'-0"



SECTION VIEW FOR 2nd POUR
Scale: 1/2" = 1'-0"

Notes:

1. This detail can be used in lieu of wood forms in spans where a longitudinal deck construction joint is located.
2. Hanger straps shall not deflect reinforcing from its proper position.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/17/97	
REVISIONS	
SHA	FHWA
7-20-06	


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SPLIT PAN CONSTRUCTION FOR
STEEL FORMS WHICH REMAIN IN PLACE

STANDARD NO. BR-SS(6.43)-97-319


SHEET 1 OF 2



Note:
Reinforcing steel not
shown for clarity.

PLAN VIEW FOR SPLIT PLAN LAP

Scale: $\frac{1}{2}'' = 1'-0''$



SECTION A-A AT HANGER STRAPS

Scale: $\frac{3}{4}'' = 1'-0''$

APPROVAL	
<i>L.S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVEL. DATE: 11/17/97	
REVISIONS	
SHA	FHWA
7-20-06	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SPLIT PAN CONSTRUCTION FOR
STEEL FORMS WHICH REMAIN IN PLACE

STANDARD NO. BR-SS(6.43)-97-319


SHEET 2 OF 2

SUPER CONCRETE WORK

* - See appropriate Lap Chart.



SECTION
Scale: $\frac{3}{4}" = 1'-0"$



34" OR 42" STRAIGHT BACK

Notes:

1. Wood forms may be used in the area of the scupper as approved by the Engineer.
2. Type IA scupper shown.


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 10/22/03	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
BRIDGE DECK REINFORCEMENT
PATTERN IN SCUPPER AREA FOR
SCUPPER TYPES I & IA AT F-SHAPE PARAPET
WITH STRAIGHT BACK


STANDARD NO. BR-SS(6.44)-03-346

SHEET 1 OF 1

* - See appropriate Lap Chart.



SECTION
Scale: $\frac{3}{4}" = 1'-0"$



SECTION A-A
Scale: $\frac{3}{4}" = 1'-0"$

34" OR 42" DIAMOND BACK

Notes:

1. Wood forms may be used in the area of the scupper as approved by the Engineer.
2. Type IA scupper shown.


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 10/22/03	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
BRIDGE DECK REINFORCEMENT
PATTERN IN SCUPPER AREA FOR
SCUPPER TYPES I & IA AT F-SHAPE PARAPET
WITH DIAMOND BACK


STANDARD NO. BR-SS(6.45)-03-347

SHEET 1 OF 1

* - See appropriate Lap Chart.



SECTION
Scale: $\frac{3}{4}" = 1'-0"$



SECTION A-A
Scale: $\frac{3}{4}" = 1'-0"$

34" OR 42" RECESSED BACK

Notes:

1. Wood forms may be used in the area of the scupper as approved by the Engineer.
2. Type IA scupper shown.


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 10/22/03	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
BRIDGE DECK REINFORCEMENT
PATTERN IN SCUPPER AREA FOR
SCUPPER TYPES I & IA AT F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.46)-03-348

SHEET 1 OF 1



SECTION

Scale: $\frac{3}{4}" = 1'-0"$

Notes:

1. All longitudinal bars are #5 spaced as shown and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multi-span bridge.
2. All keys are nominal size.
3. Portions of normal longitudinal deck steel and truss bars are not shown.
4. W.P. = Working Point.
5. All reinforcing steel to be epoxy coated.

- * Unless otherwise indicated on "Typical Cross Section".
- ** This dimension can vary ($\frac{1}{2}" \pm$ max.) according to the form liner chosen. The Contractor must contact SHA Project Engineer to verify form liner and this dimension.
- *** Slab Depth - 1"

SIDEWALK WITH RECESSED BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 10/22/03	
REVISIONS	
SHA	FHWA
11-18-05	
11-26-07	



FHWA APPROVAL
DATE:


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

LEVEL OR LOW SIDE OF CROWN
(OR SUPERELEVATED) SECTION OF
SIDEWALK AND PARAPET WITH ARCHITECTURAL FINISH


STANDARD NO. BR-SS(6.48)-03-350

SHEET 1 OF 2





Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
 Scale: 1/2" = 1'-0"

Note:
 Normal slab reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

34" RECESSED BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
FHWA APPROVAL	.
DATE:	.


STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET WITH ARCHITECTURAL FINISH


STANDARD NO. BR-SS(6.49)-05-351A

SHEET 1 OF 2

SUPER-CONCRETE WORK



Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



Note:
 Deck overhang reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

SECTION A-A
 Scale: 1/2" = 1'-0"

34" RECESSED BACK

APPROVAL	
<i>E. Schuman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
 WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.49)-05-351A(L)

VERIFIED
 10-9-2007
 LRFD

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR 34" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349A.

Note C:

The constr. jt. between the F-shape parapet and the deck slab may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA


34" RECESSED BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.49)-05-351A

SHEET 2 OF 2



SECTION B-B FOR 34" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349A.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE:	6/11/05
REVISIONS	
SHA	FHWA
10-9-07	

34" RECESSED BACK


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 34" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.49)-05-351A(L)

SHEET 2 OF 2



Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



Note:
 Normal slab reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

42" RECESSED BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
FHWA APPROVAL	.
DATE:	.


STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
 WITH ARCHITECTURAL FINISH


STANDARD NO. BR-SS(6.49)-05-351B

SHEET 1 OF 2

SUPER-CONCRETE WORK



Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



Note:
 Deck overhang reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

42" RECESSED BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT


VERIFIED
 10-9-2007
 LRFD

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
 WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.49)-05-351B(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR 42" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349B.

Note C:

The constr. jt. between the F-shape parapet and the deck slab may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA


42" RECESSED BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.49)-05-351B

SHEET 2 OF 2



SECTION B-B FOR 42" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349B.

Note C:

The constr. jt. between the F-shape parapet and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	

42" RECESSED BACK


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT



SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND 42" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.49)-05-351B(L)

SHEET 2 OF 2



Notes:

- All #7 and #8 longitudinal bars shall be placed continuously in the barrier from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multi-span bridge.
- All reinforcement bars shall be epoxy coated.
- The Contractor has the option of substituting cast-in-place epoxy coated open coil inserts with threaded holes for the bars shown. The inserts in the back face of the parapet shall have a minimum working load tension strength of 6000 lb. and a minimum length of 4 1/2". The inserts in the front face shall have a minimum working load tension strength of 8000 lb. and a minimum length of 5 1/2". The cost of epoxy coated inserts shall be included in the pertinent Superstructure Concrete item.
- Concrete deck reinforcing steel not shown.
- Place 1/2" saw cut joints to match joint spacing of outside parapet.
- No increase in any prices bid will be allowed for barrier modifications due to roadway slope or maintenance of traffic.

* Slab depth minus 1".

42" MEDIAN

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA

FHWA APPROVAL
DATE:


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

42" F-SHAPE MEDIAN BARRIER FOR BRIDGE
WITHOUT LONGITUDINAL JOINT WHERE TRAFFIC WILL
USE AREA PRIOR TO PLACING BARRIER

STANDARD NO. BR-SS(6.50)-03-352


SHEET 1 OF 1

SUPER CONCRETE WORK



Note B:
Station for light post support bracket shown on Plans is only approximate. 4" Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at 4" of pier, eliminate the control joint at the 4" of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

PLAN
Scale: 1/2"=1'-0"



SECTION A-A
Scale: 1/2"=1'-0"

Note:
Normal deck reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.5I)-05-353

SHEET 1 OF 2



Note B:
Station for light post support bracket shown on Plans is only approximate. φ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at φ of pier, eliminate the control joint at the φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A

Scale: 1/2"=1'-0"

For Section "B-B" see Sheet 2 of 2.

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

SIDEWALK WITH STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.5I)-05-353(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.21)-03-106.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.51)-05-353

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.21)-03-106.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	.
.	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.51)-05-353(L)


SHEET 2 OF 2

SUPER-CONCRETE WORK



PLAN
Scale: 1/2"=1'-0"

Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
Scale: 1/2"=1'-0"

Note:
Normal deck reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.

FHWA APPROVAL
DATE:


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.52)-05-354


SHEET 1 OF 2

SUPER-CONCRETE WORK



PLAN
Scale: 1/2"=1'-0"

Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
Scale: 1/2"=1'-0"

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.52)-05-354(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.21)-03-106.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK WITH STRAIGHT BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.52)-05-354

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.21)-03-106.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK WITH STRAIGHT BACK

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	.
.	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.52)-05-354(L)

SHEET 2 OF 2


SUPER-CONCRETE WORK



Note B:
Station for light post support bracket shown on Plans is only approximate. Φ Bracket to be located midway between parapet control joints.
A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations).
If a light post is placed at Φ of pier, eliminate the control joint at the Φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:
Normal slab reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.



SIDEWALK WITH DIAMOND BACK


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH DIAMOND BACK AND SIDEWALK

STANDARD NO. BR-SS(6.53)-05-355


SHEET 1 OF 2



Note B:
Station for light post support bracket shown on Plans is only approximate. Φ Bracket to be located midway between parapet control joints.
A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations).
If a light post is placed at Φ of pier, eliminate the control joint at the Φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.



SECTION A-A
Scale: $\frac{1}{2}''=1'-0''$

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	.
1-9-08	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH DIAMOND BACK AND SIDEWALK


STANDARD NO. BR-SS(6.53)-05-355(L)

SHEET 1 OF 2



SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2" = 1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.26)-03-161.

Note C:

The constr. jt. between the sidewalk and the deck slab may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.
FHWA APPROVAL	
DATE: 3-19-85	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH DIAMOND BACK AND SIDEWALK

STANDARD NO. BR-SS(6.53)-05-355

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2" = 1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.26)-03-161.

Note C:

The constr. jt. between the sidewalk and the deck slab may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	.
.	.
.	.
FHWA APPROVAL	
DATE: 3-19-85	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH DIAMOND BACK AND SIDEWALK

STANDARD NO. BR-SS(6.53)-05-355(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK




Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:
Normal slab reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN
Scale: 1/2" = 1'-0"



SECTION A-A
Scale: 1/2" = 1'-0"

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH DIAMOND BACK


APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
FHWA APPROVAL	.
DATE:	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH DIAMOND BACK AND SIDEWALK

STANDARD NO. BR-SS(6.54)-05-356

SHEET 1 OF 2



Note B:
Station for light post support bracket shown on Plans is only approximate. Φ Bracket to be located midway between parapet control joints.
A= Normal parapet control joint spacing (Adjust as necessary to meet minimum limitations).
If a light post is placed at Φ of pier, eliminate the control joint at the Φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

SECTION A-A
Scale: $\frac{1}{2}''=1'-0''$

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH DIAMOND BACK AND SIDEWALK

STANDARD NO. BR-SS(6.54)-05-356(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.26)-03-161.

Note C:

The constr. jt. between the sidewalk and the deck slab may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
.	.
.	.
.	.

FHWA APPROVAL
DATE: .

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH DIAMOND BACK AND SIDEWALK

STANDARD NO. BR-SS(6.54)-05-356

SHEET 2 OF 2

SUPER-CONCRETE WORK

Note:
Conduit, drain tubes and cap
may be galvanized steel or PVC.



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2" = 1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.26)-03-161.

Note C:

The constr. jt. between the sidewalk and the deck slab may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

SIDEWALK WITH DIAMOND BACK

APPROVAL	
<i>L. S. Friedman</i> DIRECTOR	OFFICE OF BRIDGE DEVEL.
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	.
.	.
.	.
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET
WITH DIAMOND BACK AND SIDEWALK


STANDARD NO. BR-SS(6.54)-05-356(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK



Note B:
Station for light post support bracket shown on Plans is only approximate. Φ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at Φ of pier, eliminate the control joint at the Φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
Scale: $\frac{1}{2}$ " = 1'-0"

Note:
Normal deck reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.
FHWA APPROVAL	.
DATE:	.


RECESSED BACK WITH SIDEWALK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET WITH
ARCHITECTURAL FINISH AND SIDEWALK


STANDARD NO. BR-SS(6.55)-05-357

SHEET 1 OF 2

SUPER-CONCRETE WORK



Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
Scale: 1/2" = 1'-0"

For Section "B-B" see Sheet 2 of 2.

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

RECESSED BACK WITH SIDEWALK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET WITH
ARCHITECTURAL FINISH AND SIDEWALK

STANDARD NO. BR-SS(6.55)-05-357(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.48)-03-350.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated.

For exact details and location of the joint see "Superstructure" Sheet.

RECESSED BACK WITH SIDEWALK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA


FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET WITH
ARCHITECTURAL FINISH AND SIDEWALK

STANDARD NO. BR-SS(6.55)-05-357

SHEET 2 OF 2



SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2" = 1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.48)-03-350.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

RECESSED BACK WITH SIDEWALK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET WITH
ARCHITECTURAL FINISH AND SIDEWALK


STANDARD NO. BR-SS(6.55)-05-357(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK



Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



Note:
 Normal slab reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

SECTION A-A
 Scale: 1/2" = 1'-0"

34" RECESSED BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
.	.

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT


SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.56)-05-358A

SHEET 1 OF 2

FHWA APPROVAL
DATE:

SUPER-CONCRETE WORK




Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.



STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

SHEET 1 OF 2



SECTION B-B FOR 34" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349A. Note C:

The constr. jt. between the F-shape parapet and the deck slab may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA


34" RECESSED BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.56)-05-358A

SHEET 2 OF 2



SECTION B-B FOR 34" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349A. Note C:

The constr. jt. between the F-shape parapet and the deck slab may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL
DATE:

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	

34' RECESSED BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT



SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.56)-05-358A(L)

SHEET 2 OF 2

12#9's, epoxy coated, spaced as shown, top and bottom placed parallel to normal slab steel. Hook one end.

Provide slip hole or drill and tap box for 1/4" ϕ conduit.

ϕ 3" ϕ conduits, full length of bridge.

#5 \square epoxy coated.

ϕ Parapet control joint

5-#5 \square Ties

Spacing to match that of normal deck steel (Varies 5" to 7"). Bars to be placed between normal deck steel.

8-#5 \square Ties, epoxy coated, @ 8" c/c. See Sheet 2 of 2.

2-#5 straight bars epoxy coated

ϕ Parapet control joint

Note B:
Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.

Note:
Normal slab reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

PLAN
Scale: 1/2" = 1'-0"

6" x 6" x 8" galvanized cast iron, galvanized steel or fiberglass U.L. listed junction boxes with cover. Provide holes in box for 3" ϕ conduit.

ϕ 3" ϕ conduits

#5- \square Ties

#5 \square Ties. See Sheet 2 of 2.

1/2" ϕ Drain at low point of junction box.

Sleeves for anchor bolts. See "Note A."

Bottom to match underside of fascia, parallel to grade.

SECTION A-A

Scale: 1/2" = 1'-0"

For Section "B-B" see Sheet 2 of 2.

42" RECESSED BACK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
1-9-08	.
.	.
FHWA APPROVAL	.
DATE:	.


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH


STANDARD NO. BR-SS(6.56)-05-358B

SHEET 1 OF 2

SUPER-CONCRETE WORK



Note B:
 Station for light post support bracket shown on Plans is only approximate. ϕ Bracket to be located midway between parapet control joints.
 A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
 If a light post is placed at ϕ of pier, eliminate the control joint at the ϕ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



Note:
 Deck overhang reinforcing steel not shown.

Note A:
 Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA
10-9-07	
1-9-08	
FHWA APPROVAL	
DATE:	


STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
 WITH DUAL CONDUITS AND 34" F-SHAPE PARAPET
 WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.56)-05-358A(L) SHEET 1 OF 2

VERIFIED
 10-9-2007
 LRFD

SUPER-CONCRETE WORK



SECTION B-B FOR 42" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349B.

Note C:

The constr. jt. between the F-shape parapet and the deck slab may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL

DATE:

APPROVAL

L. S. Friedman DIRECTOR
OFFICE OF BRIDGE DEVEL.

DATE: 6/11/05

REVISIONS

SHA FHWA

.

.

.

.

42" RECESSED BACK


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.56)-05-358B

SHEET 2 OF 2

SUPER-CONCRETE WORK



SECTION B-B FOR 42" F-SHAPE BARRIER

Scale: 1/2"=1'-0"

Note:

All #7 and #8 bars shall be placed continuously in the parapet from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.47)-03-349B.

Note C:

The constr. jt. between the F-shape parapet and the deck slab may vary slightly from the joint indicated. For exact details and location of the joint see "Superstructure" Sheet.

FHWA APPROVAL

DATE:

APPROVAL

E. S. Friedman DIRECTOR
OFFICE OF BRIDGE DEVEL.

DATE: 6/11/05

REVISIONS

SHA	FHWA
10-9-07	

42" RECESSED BACK

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND 42" F-SHAPE PARAPET
WITH ARCHITECTURAL FINISH

STANDARD NO. BR-SS(6.56)-05-358B(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK





SECTION B-B FOR SIDEWALKS WITH PARAPET

Scale: 1/2"=1'-0"

Note:

All longitudinal bars are #5's and shall be placed continuously in the sidewalk from expansion opening to expansion opening in a simple span bridge and expansion opening to centerline of pier in a multispan bridge. Refer to BR-SS(6.48)-03-350.

Note C:

The constr. jt. between the sidewalk and the deck may vary slightly from the joint indicated.
For exact details and location of the joint see "Superstructure" Sheet.

RECESSED BACK WITH SIDEWALK

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/11/05	
REVISIONS	
SHA	FHWA
10-9-07	

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT




SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH DUAL CONDUITS AND PARAPET WITH
ARCHITECTURAL FINISH AND SIDEWALK

STANDARD NO. BR-SS(6.57)-05-359(L)

SHEET 2 OF 2

SUPER-CONCRETE WORK






* * Number, shape and size of bars is contingent upon the height and style of parapet that is chosen. See Typical Section for details.

* Number of spaces to be determined by the Contractor based on the skew angle as part of the Shop Drawing Process.

PLAN

Scale: 1" = 1'-0"

Note:
Dashed area of reinforcing to be eliminated in transition area.



REINFORCING PATTERN FOR TRANSITION AREA ONLY

Notes:

1. All reinforcing steel to be epoxy coated.
2. Compression seal not shown.

APPROVAL	
<i>L. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 1/18/05	
REVISIONS	
SHA	FHWA

FHWA APPROVAL
DATE:

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PARAPET REINFORCING STEEL
PLACEMENT AT EXPANSION JOINT

STANDARD NO. BR-SS(6.58)-05-361

SHEET 1 OF 1

Entered between reinforcement


Finished roadway

3" min.

Additional 6 - #5 bars 5'-0" long placed as shown at each post

A A

Scale: 1" = 1'-0"



Scale: 1" = 1'-0"

* In order to insure a smooth and acceptable surface, Section 420.03.11 (Construction joints) will be strictly adhered to.

** May vary with application.

(USE WITH STD. NO. BR-SS(5.07)-07-375)

1. All longitudinal bars are #5 spaced as shown.
2. Normal concrete deck reinforcing not shown.
3. All reinforcing steel shall be epoxy coated.

APPROVAL	
<i>C.S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 2/8/07	
REVISIONS	
SHA	FHWHA
8-3-07	.
.	.
.	.
.	.



STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

BRIDGE DECK CURB DETAIL

STANDARD NO. BR-SS(6.59)-07-376

SHEET 1 OF 1

SUPER CONCRETE WORK



SECTION A-A
Scale: 3/4" = 1'-0"

Notes:

1. The cost of curb including reinforcing, 4" dia. PVC and AASHTO I53 Type I joint seal will be included in Superstructure Concrete item.
2. The cost of anchor bolts and plates will be included in the Railing item.
3. All reinforcing steel shall be epoxy coated.
4. Longitudinal reinforcing steel in the precast slab panel not shown.
5. Prestressing strands in the precast slab panel not shown.
6. For size and spacing of precast slab panel stirrups see precast slab panel details.

* May vary with application.

(USE WITH STD. NO. BR-SS(5.07)-07-375)

APPROVAL	
<i>L. S. Friedman</i> DIRECTOR	OFFICE OF BRIDGE DEVEL.
DATE: 2/8/07	
REVISIONS	
SHA	FHWA
8-3-07	
7-21-08	
FHWA APPROVAL	
DATE:	


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

PRECAST CONCRETE SLAB PANEL
CURB DETAIL

STANDARD NO. BR-SS(6.60)-07-377


SHEET 1 OF 1

SUPER CONCRETE WORK



Note:
For effective spans less than 5'-9" see Note 3 on Std. No. BR-SS(6.11)-79-90(L).

HL-93 TYPE XXXI SLAB
5'-9" TO 6'-0" EFFECTIVE SPAN
Scale: 1/2"=1'-0"



Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90(L)).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus O. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.
- Refer to BR-SS(6.11)-79-90(L) for overhang design requirements.

FHWA APPROVAL
DATE: 4-23-08

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 4/23/08	
REVISIONS	
SHA	FHWA

Note:
Slanted lettering indicates notes "For Office Use Only".



STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE XXXI AND XXXII
BRIDGE DECK SLABS
HL-93 LOADING



STANDARD NO. BR-SS(6.61)-08-385(L)

SHEET 1 OF 1

SUPER CONCRETE WORK



Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90(L)).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus ○. See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.
- Refer to BR-SS(6.11)-79-90(L) for overhang design requirements.

FHWA APPROVAL
DATE: 4-23-08

APPROVAL	
<i>E.S. Friedman</i> DIRECTOR	OFFICE OF BRIDGE DEVEL.
DATE: 4/23/08	
REVISIONS	
SHA	FHWA

STANDARD NO. BR-SS(6.62)-08-386(L)



STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE XXXIII AND XXXIV
BRIDGE DECK SLABS
HL-93 LOADING

Note:

Slanted lettering indicates notes
"For Office Use Only".



SHEET 1 OF 1



Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90(L)).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus \circ . See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.
- Refer to BR-SS(6.11)-79-90(L) for overhang design requirements.

FHWA APPROVAL
DATE: 4-23-08

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 4/23/08	
REVISIONS	
SHA	FHWA

STANDARD NO. BR-SS(6.63)-08-387(L)


STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE XXXV AND XXXVI
BRIDGE DECK SLABS
HL-93 LOADING

SHEET 1 OF 1


Note:

Slanted lettering indicates notes
"For Office Use Only".





HL-93 TYPE XXXVII SLAB
GREATER THAN 8'-3" TO 8'-9" EFFECTIVE SPAN
Scale: 3/8"=1'-0"



HL-93 TYPE XXXVIII SLAB
GREATER THAN 8'-9" TO 9'-8" EFFECTIVE SPAN
Scale: 3/8"=1'-0"

Note:

- All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
- Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90(L)).
- All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
- On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus \odot . See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.
- Refer to BR-SS(6.11)-79-90(L) for overhang design requirements.

FHWA APPROVAL
DATE: 4-23-08

APPROVAL	
<i>E.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVEL.	
DATE: 4/23/08	
REVISIONS	
SHA	FHWA


STANDARD NO. BR-SS(6.64)-08-388(L)

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT
TYPE XXXVII AND XXXVIII
BRIDGE DECK SLABS
HL-93 LOADING



SHEET 1 OF 1

SUPER CONCRETE WORK



HL-93 TYPE XXXIX SLAB
GREATER THAN 9'-8" TO 10'-0" EFFECTIVE SPAN
 Scale: 3/8"=1'-0"

Note:

1. All steel sizes and spacing based on ASTM A-615, Grade 60 (fs=24,000 p.s.i.).
2. Transverse bars to be placed normal to center line of stringers. (For curved girder see BR-SS(6.11)-79-90(L)).
3. All longitudinal bars are to be #5's placed as shown except if Note 4 requires and indicates larger bars.
4. On continuous bridges, over piers, additional longitudinal steel is to be added to the top of the slab between normal bars and is indicated thus \bigcirc . See Detail No. BR-SS(6.30)-88-195 for the lengths and size of these additional bars.
5. Refer to BR-SS(6.11)-79-90(L) for overhang design requirements.

Note:

Slanted lettering indicates notes
 "For Office Use Only".

APPROVAL	
<i>E. S. Friedman</i>	DIRECTOR
	OFFICE OF BRIDGE DEVEL.
DATE: 4/23/08	
REVISIONS	
SHA	FHWA

FHWA APPROVAL
 DATE: 4-23-08

STATE OF MARYLAND
 DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 OFFICE OF BRIDGE DEVELOPMENT

TYPE XXXIX BRIDGE DECK SLAB
 HL-93 LOADING

STANDARD NO. BR-SS(6.65)-08-389(L)

SHEET 1 OF 1



SUPER CONCRETE WORK